



# FRAZIER PARK PUBLIC UTILITY DISTRICT



MAILING ADDRESS: PO BOX 1525  
TELEPHONE: (661) 245-3734 FAX: (661) 245-3472  
www.frazierparkwater.com

## Mainline Extension Policy

Approved by the FPPUD Board of Directors on 2-13-2007

### I) The developer will supply the following:

- a. Engineering plans for the project based on District standards (USDA project plans and specifications).
- b. Bond estimate prepared by developer's engineer, based on the current F.P.P.U.D. Bond Estimate Rate Sheet.
- c. A check for 5% of the bond amount to cover administrative costs and engineer's fee for reviewing and approval of plans. (2% administrative cost to the District and 3% Engineer fees).

### II) Following approved Plan Check, the developer will supply the following:

- d. Proof of 100% Performance and Payment Bond based on 100% bond amount, to be held for 1 year by the District following the date of completion of the project.
- e. Insurance Certificate for Liability for no less than \$1,000,000.00
- f. Proposed construction schedule
- g. Contractor's proof of Worker's Compensation coverage.
- h. A check in the amount of 6% of the bond amount to cover inspection fees and inspection of "As Built" plans by our District Engineer.
- i. Developer to pay District connection fees for each connection.
- j. District will issue "Will Serve" letters for all connections that have been paid for after items a-i have been completed.
  1. District inspector to be present for installation by Contractor of pipe, hydrants, etc. prior to backfill, after pipe shading but prior to backfill above shading. Provide compaction tests to District to obtain clearance for start of pressure testing and disinfection. Pressure testing, disinfection of the new line and bacteriological testing will be the responsibility of the Contractor, and must be done while the District's inspector is present.
  2. Final Inspection and tie-in to District water system. District inspector must be present at all tie-ins. Contractor to complete all Punch List items as requested by District.

### III) Following Final Inspection:

- k. Developer will supply a complete set of "As Built" plans for approval.
- l. After "As Built" plans are accepted as completed by the District, meters will be installed at the addresses with approved "Will Service Letters".

*Special District since 1939 - Serving Water to the Frazier Park Community*



# FRAZIER PARK PUBLIC UTILITY DISTRICT



MAILING ADDRESS: PO BOX 1525  
TELEPHONE: (661) 245-3734 FAX: (661) 245-3472

## Frazier Park PUD Bond Estimate Rate Sheet 2/14/2007

Item	Unit	Unit Price
Furnish and install 10 inch PVC (CL-150) waterline and appurtenances	L.F.	\$136.50
Furnish and install 8 inch PVC (CL-150) waterline and appurtenances	L.F.	\$130.00
Furnish and install 6 inch PVC (CL-150) waterline and appurtenances	L.F.	\$80.00
Furnish and install 6 inch PVC (CL-200) waterline and appurtenances	L.F.	\$85.00
Furnish and install 6 inch PVC (CL-150 waterline complete with 12" casing and appurtenances).	L.F.	\$850.00
Furnish and install 6 inch PVC (CL-200 waterline complete with 12" casing and appurtenances).	L.F.	\$800.00
Furnish and install 2 inch PVC (Sch 40) waterline and appurtenances	L.F.	\$67.30
Furnish and install 1 inch PVC (Sch 80) waterline and appurtenances	L.F.	\$57.20
Furnish and install 10 inch gate valves (flanged) and appurtenances	Each	\$4,000.00
Furnish and install 8 inch gate valves (flanged) and appurtenances	Each	\$3,720.00
Furnish and install 6 inch gate valves (flanged) and appurtenances	Each	\$2,875.00
Furnish and install 2 inch gate valves (flanged) and appurtenances	Each	\$2,340.00
Furnish and install 6 inch Fire hydrant assy. and appurtenances (dry barrel)	Each	\$5,305.00
Furnish and install 3/4" water service line from new mains to new water meter and all appurtenances	Each	\$1,000.00
Furnish and install water service line from new mains to existing water meter	Each	\$975.00
Furnish and install 1 inch air/vac assembly and appurtenances	Each	\$4,900.00
Sawcut pavement, including replacement blades (2 cuts per LF)	L.F.	\$62.50
Asphalt trench repair, including temp. cold mix, base replacement, plant hot mix, and seal coat.	Sq. Ft.	\$35.00
Chainlink Security Fencing (including gates)	L.F.	\$60.00

**COSTS FOR ADDITIONAL ITEMS MAY NEED TO BE DETERMINED INDIVIDUALLY**

*Special District since 1939 - Serving Water to the Frazier Park Community*